

NOTES TO BIDDERS:

- The contractor is required to carefully plane around all manholes, water valves, and catch basins in the designated areas set for planing. All such appurtenance outside of the planed areas shall adjusted to grade by the contractor with risers supplied by the City. All such appurtenances shall be field-marked by the City before the bid.
- Excavate existing pavement 12” in depth. Install stabilization fabric. Construct 6” No. 1 & No. 2 limestone base. Construct an ODOT 304 2” limestone aggregate base. Construct a 2.5” asphalt concremented base. Install 1.5” asphalt concrete surface course, type 1.
- Construct a 1,200’ PA curb (wedge curb), preferred.
- Retainment shall be 8% for the first 50% of the job and shall be held until all work is satisfactorily completed.
- The city has the right to select among the bid items and add to the bid, or deduct quantities listed and at the unit prices stated in the bid.
- All bidders must be ODOT prequalified.
- The contractor must complete the work by August 31st, 2025.
- State Prevailing Wage Rates apply to this project.
- The contractor shall supply plate test asphalt samples as directed by the City.
- Liquidated damages for \$500.00 per day shall be applied for failure to complete the job in the period specified above.
- Once the contractor begins work in the City, all work under this contract shall be daily and continuous, except weekends (unless the contractor chooses to work on Saturday only), or unless disruptions are due to significant breakdowns, labor strikes, adverse weather, or some other valid reason.
- The ODOT “Placing Index” (ODOT 401.20, as well as other sections as they pertain to fuel, concrete, steel, etc.) is specifically excluded from these specifications and contracts. If there is any conflict between this section and other sections here, or between this section and the ODOT Construction and Material Specifications, this section shall govern.
- All seams and joints must be sealed.